

TABELA 2. ELEMENTY TRASY W PLANIE

Przebudowa drogi gminnej nr 41306C (dz. 183) obręb Szywnałów - etap 1

ELEMENT	OD	DO			
Prosta	0+000,00	0+001,19	L=1,19m		
Łuk kołowy	0+001,19	0+015,40	R=20,00m	T=7,42m	B=1,33m
			L=14,21m	g=0,7107rd	g=45,2437g
Prosta	0+015,40	0+058,48	L=43,08m		
Łuk kołowy	0+058,48	0+106,74	R=210,00m	T=24,24m	B=1,39m
			L=48,26m	g=0,2298rd	g=14,6307g
Prosta	0+106,74	0+335,15	L=228,40m		
Łuk kołowy	0+335,15	0+409,81	R=700,00m	T=37,37m	B=1,00m
			L=74,66m	g=0,1067rd	g=6,7901g
Prosta	0+409,81	0+448,41	L=38,61m		
Prosta	0+448,41	0+610,68	L=162,27m		
Łuk kołowy	0+610,68	0+645,84	R=500,00m	T=17,59m	B=0,31m
			L=35,16m	g=0,0703rd	g=4,4773g
Prosta	0+645,84	0+663,35	L=17,51m		
Łuk kołowy	0+663,35	0+702,18	R=100,00m	T=19,66m	B=1,91m
			L=38,83m	g=0,3883rd	g=24,7183g
Prosta	0+702,18	0+726,02	L=23,84m		
Łuk kołowy	0+726,02	0+745,91	R=100,00m	T=9,98m	B=0,50m
			L=19,89m	g=0,1989rd	g=12,6616g
Prosta	0+745,91	0+798,39	L=52,49m		
Łuk kołowy	0+798,39	0+851,60	R=180,00m	T=26,80m	B=1,98m
			L=53,20m	g=0,2956rd	g=18,8172g
Prosta	0+851,60	0+892,97	L=41,37m		
Łuk kołowy	0+892,97	0+940,41	R=60,00m	T=25,04m	B=5,01m
			L=47,44m	g=0,7906rd	g=50,3343g
Prosta	0+940,41	0+989,98	L=49,57m		