

TABELA 2. ELEMENTY TRASY W PLANIE

Przebudowa drogi gminnej nr 41302C (dz. 46/2) obręb Szywnałów - etap 1

ELEMENT	OD	DO			
Prosta	0+000,00	0+000,61	L=0,61m		
Łuk kołowy	0+000,61	0+022,81	R=30,00m	T=11,64m	B=2,18m
			L=22,20m	g=0,7400rd	g=47,1070g
Prosta	0+022,81	0+190,07	L=167,26m		
Prosta	0+190,07	0+338,30	L=148,23m		
Łuk kołowy	0+338,30	0+428,49	R=500,00m	T=45,21m	B=2,04m
			L=90,18m	g=0,1804rd	g=11,4827g
Prosta	0+428,49	0+498,37	L=69,88m		
Łuk kołowy	0+498,37	0+533,85	R=500,00m	T=17,75m	B=0,31m
			L=35,48m	g=0,0710rd	g=4,5179g
Prosta	0+533,85	0+578,33	L=44,48m		
Łuk kołowy	0+578,33	0+595,92	R=300,00m	T=8,80m	B=0,13m
			L=17,59m	g=0,0586rd	g=3,7335g
Prosta	0+595,92	0+640,74	L=44,82m		
Łuk kołowy	0+640,74	0+663,55	R=1000,00m	T=11,40m	B=0,07m
			L=22,81m	g=0,0228rd	g=1,4520g
Prosta	0+663,55	0+751,69	L=88,14m		
Łuk kołowy	0+751,69	0+823,48	R=160,00m	T=36,51m	B=4,11m
			L=71,80m	g=0,4487rd	g=28,5666g
Prosta	0+823,48	0+826,21	L=2,72m		
Łuk kołowy	0+826,21	0+873,82	R=100,00m	T=24,26m	B=2,90m
			L=47,61m	g=0,4761rd	g=30,3086g
Prosta	0+873,82	0+897,66	L=23,85m		
Łuk kołowy	0+897,66	0+963,12	R=500,00m	T=32,78m	B=1,07m
			L=65,46m	g=0,1309rd	g=8,3343g
Prosta	0+963,12	0+966,84	L=3,72m		
Łuk kołowy	0+966,84	1+033,56	R=100,00m	T=34,66m	B=5,84m
			L=66,72m	g=0,6672rd	g=42,4781g
Prosta	1+033,56	1+039,55	L=5,99m		